



818 S. FLORES ST. ① SAN ANTONIO, TEXAS 78204 ① www.saha.org

Procurement Department

ADDENDUM #3

To: 1003-909-62-3163

RFQ for Repairs at 11206 Prairie Springs

Date: April 16, 2010

Question 1: Will new counters you are providing have a backsplash? If so, will the electrical duplex outlet currently located in the backsplash to the right of the sink be cut out by the supplier or will we be required to cut the backsplash to fit in the duplex outlet? Another option is to face the outlet toward the dining room in the drywall under the pass-thru counter. And yet another option is to abandon the outlet.

Answer 1: The new countertop will have a backsplash. The contractor will be required to cut the opening for the duplex electrical outlet. The outlet will remain in the current position.

Question 2: The storage building in the back yard is scheduled to be removed. It sits on a concrete slab. Do we include removal of the concrete slab?

Answer 2: No, leave the concrete slab in place.

By: Charles R Bode
Charles Bode, Asst. Director of Procurement

Date: April 16, 2010