



818 S. FLORES ST. ① SAN ANTONIO, TEXAS 78204 ① www.saha.org

Procurement Department

ADDENDUM #3

To: 1009-913-75-3333
RFP for Repair of Parking Lot at Woodhill
Date: November 1, 2010

Question 1: What is the total square foot of repair per the whole project?

Answer 1: The estimated total for repair is 18, 569 square feet. The contractor must verify all dimensions.

Question 2: What is the total square foot for the seal coating?

Answer 2: The entire parking lot shall be sealed and striped, approximately 202,254 square feet

Question 3: Are we able to seal coat & patch at the same time?

Answer 3: The area to be repaired must be completed per the manufacturer's specification and the specification of the RFP prior to seal coating.

Question 4: How much compact action will be needed for density?

Answer 4: Contractor must fill to level with original base material and mechanically compact to 95% with stabilized #2 1-1/2 to dust crushed limestone base material meeting TXDOT Standard Specification.

Question 5: What type of crack code required (hot or cold)?

Answer 5: Hot per the specifications.

Question 6: Is this project going to be in phases on the parking lot?

Answer 6: Yes, to accommodate the residents, the repairs will be completed in sections.

By: *Carl Bottoms*

Date: November 1, 2010

Procurement Supervisor