



818 S. FLORES ST. ① SAN ANTONIO, TEXAS 78204 ① www.saha.org

Procurement Department

ADDENDUM #2

To: RFQ# 1107-988-15-3563
RFQ for Repair the Gates at Wheatley
Date: August 16, 2011

The specifications are amended as follows:

Corner post shall be buried a minimum of 36 inches or to the original height.
Line posts shall be straightened or removed, straightened and reinforced with concrete as required. Line posts shall be buried a minimum of 24 inches or to original height.
Line posts shall be welded where required.
Handicap rails shall be straightened and secured.

By: Carl Bottoms
Procurement Supervisor

Date: August 16, 2011